



Bill Of Material 4' x 25' With Handrail

Qty.	Description
5	4' H x 5' W Galvanized Steel Panels
6	3" x 7' 0" GRS Pipe, Threaded One End
6	3" x 3' 6" GRS Pipe For Handrail W/ Cplng
6	Cast Pipe Cap
55'	Handrail Cable
5	Yellow Cable Guard
2	Galvanized Steel Anchor
4	10' Anchor Cable
24	Cable Clamps
2	1/2" x 4 1/2" Eye Bolt (for lifting)

Note:

Stencil panels with individual weight:
4' PANEL 235 LBS.



Dixie Precast, Inc.
www.dixieprecast.com
2950 Angelette Drive 770-944-1930
Austell, Georgia 30106 Fax (770) 944-9136

4' H x 25' Steel Retaining Wall
With Safety Rail

Drawn By:
VRS

Date:
09/23/2009

THIS PRODUCT IS COVERED BY ONE OR MORE US PATENTS

THIS PRINT REPRESENTS A PROPRIETARY PRODUCT AND IS OWNED BY DIXIE PRECAST, INC. FOR THE USE OF ITS CUSTOMERS AND IS NOT TO BE CONVEYED, NOR COPIED BY ANY OTHER PARTY WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE OWNER.

Rev. #
1

Sheet 1 of 1