



Bill Of Material 6' x 30' Without Handrail

Qty.	Description
6	6' H x 5' W Galvanized Steel Panels
7	3" x 10' 6" Galvanized Steel Pipe
7	Cast Pipe Cap
3	Galvanized Steel Anchor
5	15' Anchor Cable
20	Cable Clamps
2	1/2" x 4 1/2" Eye Bolt (for lifting)

Note:

Stencil panels with individual weight:  
6' PANEL 340 LBS.

	<b>Dixie Precast, Inc.</b> <a href="http://www.dixieprecast.com">www.dixieprecast.com</a>	
	2950 Angelette Drive Austell, Georgia 30106	770-944-1930 Fax (770) 944-9136

6'H x 30' Steel Retaining Wall  
Without Rail

Drawn By: <b>VRS</b>	Date: <b>02/03/2011</b>
-------------------------	----------------------------

THIS PRODUCT IS COVERED BY ONE OR MORE US PATENTS

THIS PRINT REPRESENTS A PROPRIETARY PRODUCT AND IS OWNED BY DIXIE PRECAST, INC. FOR THE USE OF ITS CUSTOMERS AND IS NOT TO BE CONVEYED, NOR COPIED BY ANY OTHER PARTY WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE OWNER.

Rev. # <b>0</b>	Sheet 1 of 1
--------------------	--------------